

Republic of the Philippines MUNICIPALITY OF KAPALONG Province of Davao del Norte 000

INVITATION TO BID

CONSTRUCTION OF BIOSECURED SWINE FACILITY (FINISHER TYPE) AT APC PRK. 8-A, BRGY. CAPUNGAGAN, KAPALONG, DAVAO DEL NORTE

- 1. The Local Government Unit of Kapalong, through the DA Livestock Program FY 2023 intends to apply the sum of Three Million One Hundred Forty Thousand Pesos Only (P 3,140,000.00) Construction of Biosecured Swine Facility (Finisher Type) at APC Prk. 8-A, Brgy. Capungagan, Kapalong, Davao del Norte / 010-2023 being the Approved Budget for the Contract (ABC) to payments under the contract for each lot. Bids received in excess of the ABC for each lot shall be automatically rejected at bid opening.
- 2. The Local Government Unit of Kapalong now invites bids for the above Procurement Project. Completion of the Works is required **90** calendar days (Including 10 unworkable Days). Bidders should have completed a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
- 3. Bidding will be conducted through open competitive bidding procedures using non-discretionary "pass/fail" criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.
- 4. Interested bidders may obtain further information from Local Government Unit of Kapalong and inspect the Bidding Documents at the address given below from 8:00 A.M. to 5:00 PM.
- 5. A complete set of Bidding Documents may be acquired by interested bidders on October 9, 2023 from given address and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB, in the amount of (P 5,000.00). The Procuring Entity shall allow the bidder to present its proof of payment for the fees will be presented in person during bid opening as part of Eligibility Requirements.
- 6. The Local Government Unit of Kapalong will hold a Pre-Bid Conference¹ on **October 16**, **2023 at 1:30 PM** at **Supply Office LGU Compound Maniki, Kapalong**, which shall be open to prospective bidders.
- 7. Bids must be duly received by the BAC Secretariat through (i) manual submission at the office address as indicated below, on or before **November 6, 2023 at 10:30 A.M.** Late bids shall not be accepted.
- 8. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB** Clause 15.

May be deleted in case the ABC is less than One Million Pesos (PhP1,000,000) where the Procuring Entity may not hold a prebid conference.

- 9. Bid opening shall be on **November 6, 2023 at 10:30 A.M** at the given address below **.**Bids will be opened in the presence of the bidders' representatives who choose to attend the activity.
 - 10. Interested Bidders shall submit Letter of Intent (LOI) and Notarized Authorization as representative from the proprietor to attend the Bid Opening.
- 11. The Local Government Unit of Kapalong reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised Implementing Rules and Regulations (IRR) of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.
- 12. For further information, please refer to:

Mary Elizabeth L. Exala
Office of the Bids and Award Committee
Kapalong Municipal Hall
Municipality of Kapalong
Province of Davao del Norte
Cellphone No. 09176848162

www.kapalong.gov.ph

13. You may visit the following websites:

For downloading of Bidding Documents: www.PhilGEPS.gov.ph

(SGD.) MARY ELIZABETH L. EXALA

BAC Chairperson or Authorized Representative]

MUNICIPALITY OF KAPALONG

Province of Davao

PROJECT NAME :

CONSTRUCTION OF BIOSECURED SWINE FACILITY (FINI

LOCATION OF PROJECT:

APC Purok 8-A, Brgy. Capungagan, Kapalong, Davao del Norte

BID PROPOSAL

ITEM ESTIMATED upit PAYMENTS WITH LINIT RID				
ITEM	ESTIMATED	unit	PAYMENTS WITH UNIT BID	UNI PRIC IN
	QUANTITY		PRICES WRITTEN IN WORDS	FIGUE
А			Swine Housing	
800(1)	224.00	sq.m.	Clearing and Grubbing	
803(1)a	28.37	cu.m.	Structure Excavation (Common Soil)	
803(3)	13.45	cu.m.	Foundation Fill	
804(1)a	6.96	cu.m.	Embankment (From Structure Excavation)	
804(4)	12.76	cu.m.	Gravel Fill	
900(1)c1	22.99	cu.m.	Structural Concrete (Class A), 28 days	
902(1)a	1,468.07	kgs.	Reinforcing Steel (Deformed, Grade 40)	
903(1)	1.00	L.S.	Formworks and Falseworks	
1002(1)a	34.00	meters	Galvanized Iron Pipe with Fittings (13mm dia.)	
1002(1)0	1.00	L.S.	Steel Doors and Frames	
• •				
1013(2)a1	14.00	ln.m.	Fabricated Metal Roofing Accessory (Gauge 26, Ridge Rool)	
1027(1)	166.72	sq.m.	Cement Plaster Finish	
1032(1)c	330.62	sq.m.	Painting Works (Steel)	
1038(1)	120.00	sq.m.	Reflective Insulation CHB Load Bearing (Including Reinf. Steel,	
1046(1)a1	122.68	sq.m.	100mm)	
1047(1)	725.89	kgs.	Structural Steel	
1047(2)a	2,457.83	kgs.	Structural Steel (Trusses)	
1047(2)b	1,115.82	kgs.	Structural Steel (Purlins)	
1100(10)	1.00	L.S.	Conduits, Boxes & Fittings (Conduit Works/ Conduit Rough-in)	
1101(33)	1.00	I.S.	Wires and Wiring Devices	
1103(1)	1.00	L.S.	Lighting Fixtures and Lamps	
SPL	1.00	set	Power Spray with Complete Accessories	
SPL 2	4.00	pieces	Wet and Dry Automatic Feeder (100 Kilograms Capacity)	
SPL 3	57.55	sq.m.	Pre-painted G.I. Sheet Louver Wall	
SPL 4	104.78	sq.m.	Polyethelene Plastic Screen Wall Prepainted Metal Sheets (0.40mm, Rib Type,	
SPL 5	204.40	sq.m.	Long	
			Span)	
В.			Polyethelene Tank with Concrete Platform	
800(1)	31.36	sq.m.	Clearing and Grubbing	
803(1)a	1.94	cu.m.	Structure Excavation (Common Soil)	
803(3)	1.43	cu.m.	Foundation Fill	
804(1)a	2.05	cu.m.	Embankment (From Structure Excavation)	
804(4)	0.45	cu.m.	Gravel Fill	
900(1)a1	0.42	cu.m.	Structural Concrete (Class A), 7 days	
902(1)a	29.60	kgs.	Reinforcing Steel (Deformed, Grade 40)	
1002(1)b	18.00	meters	Galvanized Iron Pipe with Fittings (25mm dia.)	
1027(1)	6.40	sq.m.	Cement Plaster Finish CHB Load Bearing (Including Reinf. Steel,	
1046(1)a1	7.68	sq.m.	100mm)	
SPL 1	1.00	set	Polyethylene Tank , 2000 liters	
С.			Cyclone Wire Perimeter Fence and Gate	
800(1)	117.00	sq.m.	Clearing and Grubbing	

803(1)a	2.90	cu.m.	Structure Excavation (Common Soil)	
803(3)	1.38	cu.m.	Foundation Fill	

MUNICIPALITY OF KAPALONG

Province of Davao

PROJECT NAME :

CONSTRUCTION OF BIOSECURED SWINE FACILITY (FINI

LOCATION OF PROJECT:

APC Purok 8-A, Brgy. Capungagan, Kapalong, Davao del Norte

BID PROPOSAL

ITEM	ESTIMATED QUANTITY	unit	PAYMENTS WITH UNIT BID PRICES WRITTEN IN WORDS	UNIT PRICE IN FIGURES
900(1)a1	2.23	cu.m.	Structural Concrete (Class A), 7 days	
902(1)a	324.46	kgs.	Reinforcing Steel (Deformed, Grade 40)	
903(1)	1.00	L.S.	Formworks and Falseworks	
1032(1)c	16.52	sq.m.	Painting Works (Steel)	
1722(1)c	227.16	sq.m.	Fence (Cyclone Wire)	
SPL 1	1.00	each	Fencing Gates (Width, 3.00m)	
SPL 2	2.00	each	Fencing Gates (Width, 0.80m)	
D.	2.00		Waste Management Facility	
SPL 1	18.40	cu.m.	Waste Management Facility (Collecting Tank, Septic Tank, Concrete Lagoon and Earth Lagoon)	
			Feeds Storage with Shower and Ante-	
E			Room	
800(1)	73.50	sq.m.	Clearing and Grubbing	
803(1)a	18.49	cu.m.	Structure Excavation (Common Soil)	
803 (3)	4.53	cu.m.	Foundation Fill	
804(4)	7.49	cu.m.	Gravel Fill	
900(1)a1	5.19	cu.m.	Structural Concrete (Class A), 7 days	
902(1)a	719.14	kgs.	Reinforcing Steel (Deformed, Grade 40)	
903(1)	1.00	I.S.	Formworks and Falseworks	
1001 (10)	1.00	L.S.	Pipes with Fittings Connections	
1001(11)	1.00	L.S.	Septic Vault (CHB)	
1002(1)a	12.00	meters	Galvanized Iron Pipe with Fittings (13mm dia.) Water Closet , Elongated , Complete (Flush	
1002(5)b	1.00	set	Type) Urinal, Flush Valve,Complete (Push Buttom	
1002(9)a	1.00	set	Type)	
1002(14)a	1.00	set	Lavatory, Wall Hung, Complete (Manually Operated) Ceiling (4.50mm. thk. Metal Frame, Fiber	
1003(1)a1	34.55	sq.m.	Cement Board)	
1008(1) c	0.36	sq.m.	Aluminum Glass Window (Awning Type)	
1010 (2)b	7.56	sq.m.	Doors (Wood Panel)	
1013(2)a2	19.90	In.m.	Fabricated Metal Roofing Accessory (Gauge 26,	

			Flashings)	
1018(2)	2.90	sq.m.	Unglazed Tiles	
1018(5)	12.30	sq.m.	Glazed Tiles	
1027(1)	141.02	sq.m.	Cement Plaster Finish	
1032(1)a	175.57	sq.m.	Painting Works (Masonry/Concrete)	
1032(1)c	49.99	sq.m.	Painting Works (Steel)	
1043(2)	2.00	set	PVC Doors and Frames	
			CHB Load Bearing (Including Reinf. Steel	
1046(1)a1	83.88	sq.m.	,100mm)	
1047(2)b	241.02	kgs.	Structural Steel (Purlins)	
1047(8)	449.12	kgs.	Structural Steel (Roof Framing)	
1100(10)	1.00	L.S.	Conduits, Boxes & Fittings (Conduit Works/	
			Conduit Rough-in)	
1101(33)	1.00	L.S.	Wires and Wiring Devices	
1102(1)	1.00	L.S.	Panel Board with Main & Branch Breakers	
1103(1)	1.00	L.S.	Lighting Fixtures and Lamps	

MUNICIPALITY OF KAPALONG

Province of Davao

PROJECT NAME : CONSTRUCTION OF BIOSECURED SWINE FACILITY (FINI

LOCATION OF PROJECT: APC Purok 8-A, Brgy. Capungagan, Kapalong, Davao del Norte

BID PROPOSAL

		_		UNIT	
ITEM	ESTIMATED	unit	PAYMENTS WITH UNIT BID	PRICE	
	QUANTITY		PRICES WRITTEN IN WORDS	IN FIGURES	
SPL	48.95	sq.m.	Prepainted Metal Sheets (0.40mm,Rib Type,		
			Long Span)		
F.			Pathwalk and Mini Shed		
803(1)a	4.64	cu.m.	Structure Excavation (Common Soil)		
803(3)	3.23	cu.m.	Foundation Fill		
804(1)b	3.89	cu.m.	Embankment (From Borrow)		
804(4)	2.91	cu.m.	Gravel Fill		
900(1)a1	3.99	cu.m.	Structural Concrete (Class A), 7 days		
902(1)a	166.50	kgs.	Reinforcing Steel (Deformed, Grade 40)		
1027(1)	9.44	sq.m.	Cement Plaster Finish		
1032(1)c	23.47	sq.m.	Painting Works (Steel)		
			CHB Load Bearing (Including Reinf. Steel,		
1046(1)a1	12.55	sq.m.	100mm)		
1722(2)	15.20	ln.m.	Railings		
SPL 1	1.00	L.S.	Weighing Scale Shed		
G.			Other Requirement		
В.5	1.00	each	Project Billboard		
B.7 (2)	1.00	L.S.	Occupational Safety and Heath Program		

TOTAL AMOUNT O	F BID (IN FIGURES)				
TOTAL AMOUNT OF BIL	D (IN WORDS)				
Name & Signature or his duly Authoriz				N	AME OF E